

## Do you know the standards and timelines for snow removal operations on Priority 2 streets?



### Priority 2 (20 km)

Collector streets, local commercial streets, regular bus routes, etc.  
Examples: Pavillon, Sainte-Anne, Perron.

	Snow clearance	Spreading abrasives	Snow loading (streets where there are sidewalks)
For sidewalks	Once 2.5 cm has accumulated on the ground; between 2.5 and 5 cm on the ground, with simultaneous abrasive spreading	Based on visual inspections of crews on site. The operation must be completed within a maximum time limit of 4 hours.	Since the snow is piled up in the proper place along the roadway, it is removed at the same time as the snow on the roadway.
For roadways	Once 2.5 cm has accumulated on the ground	Within 3 hours maximum, if less than 2.5 cm  From the start of operations, if more than 2.5 cm	36-96 hours maximum (snowfall of 20 cm on the ground or less)

